No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
7	Fixing old slabs in surki mortar	S.ft.	83	0 2 0		
8	Carrying the old stones removed in bund above 53 : 00 and using the same for apron and wings with the required new jelly.	C.yd.	133	1 0 0		
9	Cutting joggle joints in slabs	Each joint	8	0 12 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 2nd May 1939.

Notice is hereby given to the public that the date of receipt of tenders for restoring Kyadigunte Major Tank Reg. No. 139, Pavagada Taluk, is extended to 15th May 1939 up to 2 P.M.

The earnest money required for the work is Rs. 270 which should be credited to the treasury to the head '17 (*a*) P. W. Deposits' and the chellan enclosed to the tender.

Notification dated 5th May 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Tumkur Division, up to 2 P.M., on 15th May 1939, for constructing one unit of double block of Operators' Quarters for Electrical Department at Kunigal Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained by paying Re. 0-4-0 from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for Rs. 165 for having credited to '17(a) P.W. Deposits' and be superscribed "Tender for constructing one unit of double block of Operators' Quarters at Kunigal Town" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Only 'Chamundi' brand cement should be used on works.

14. Only Mysore Teakwood should be used.

Abstract estimate for constructing a Unit of Double Block of Operator's Quarters for the Electrical Department at Kunigal Town.

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation in gravelly soil and filling in basement including watering and tamping in layers 6″ thick ..	C.yd.	0 3 6	53
2	Stone jelly (one inch size) concrete in lime mortar 1 : 2 : 4 for foundations laid in 4″ layers and well tamped	C.ft.	0 3 6	597
3	Burnt size stones in clay in courses not less than 8″ high with bond stones 6 feet apart in every course of foundations and for basement including all quoins neatly dressed 2″ wide at corners	C.ft.	0 3 6	1,079
4	Burnt brick in clay for superstructure	,,	0 3 0	1,946
5	Burnt brick in lime mortar for superstructure	,,	0 4 6	746
6	Burnt stone slabs 6″ thick set in lime mortar with two line dressing for steps and all exposed faces, etc., complete ..	S.ft.	0 5 0	249
7	Teakwood doors with 3″×4″ frame 1¼″ thick battened shutters and all necessary fixtures complete	,,	1 0 0	280
8	Teakwood windows with 3″×4″ frame 1¼″ thick battened shutters ⅝″ dia. iron bars 4″ apart and all necessary iron fixtures, etc., complete	,,	1 4 0	116
9	Teakwood wall shelves 3″×4″ frame work with 1¼″ thick battened shutters and ¾″ cross planks and all necessary iron fixture with locking arrangements, etc., complete ..	,,	1 2 0	96
10	Teakwood wrought and put up with wood oiling, two coats, etc., complete	C.ft.	5 0 0	5,155
11	Teakwood eaveboard plain 9″ deep ¾″ thick fixing complete ..	R.ft.	0 9 0	149
12	Roofing with first class Mangalore tiles on teak reepers nailed including wood oiling to reepers eave tiles being tied by a teak batten	Sqr.	25 0 0	15.00
13	Mangalore ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	78
14	Tested rolled steel girders as per B.S.S. inculding lifting and hoisting with two coats of approved paint with necessary clamps, etc., complete	Cwt.	12 0 0	6.36
15	Boxing girders with cement concrete, etc.	R.ft.	0 10 0	20
16	Roofing with brick nogge terrace filled in with brick in surki mortar with wedge shaped precast reinforced cement joist with 3″ to 6″ surki concrete, two courses of flat tiles surface and ceiling plastered with chunam, etc., complete (below 10 feet span)	Sqr.	55 0 0	3.74
17	Plain parapet wall with burnt brick in mortar 9″ thick 1½ feet to 2½ feet high including blocking course 6″ high with deep holes, 8 feet apart including plastering with chunam mortar.	R.ft.	0 10 0	60
18	Burnt brick in mortar cornice 9″ deep with 6″ projection as per design including chunam plastering	R.ft.	0 9 0	63
19	Flooring with cement concrete 1 : 2 : 4 to 1½″ thick on a bed of 6″ thick lime concrete with topping of red cement ⅜″ thick finished and cut to required pattern where required ..	Sqr.	20 0 0	9.00
20	Chunam plastering two coats, including rounding off corners and smooth rendering	,,	3 0 0	50
21	Cement pointing with thread lines after scraping the joints to ½″ to 1″ deep	,,	3 8 0	2.21
22	White and colour washing, two coats	,,	0 4 6	52.20
23	Rain water down zinc pipes 4″ diameter including suitable bell mouth at top and bent at bottom	R.ft.	0 8 0	65
24	Mortar bands—brick in mortar 9″×9″ including plastering complete	,,	0 5 0	24
25	Chocolate painting, two coats (mixed and applied as per Bombay specifications)	Sqr.	3 0 0	13.33
26	Expanded metal 3″×1½″ mesh with teak frame work including door and necessary iron fixtures, etc., complete	S.ft.	0 12 0	123
27	Constructing Chimney in kitchen	No.	50 0 0	2
28	Constructing a sink	No.	5 0 0	2
29	Providing and fixing stone mortar and pestle	No.	5 0 0	2
30	Levelling ground and clearing site, etc., and other unforeseen charges	L. S.		

Notification dated 5th May 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 15th May 1939, for constructing a block of four linemen's quarters of Electrical Department at Kunigal Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Enigneer by paying Re. 0-4-0. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury challan for Rs. 110 for having credited the earnest money to "17 (*a*) P. W. Deposits" and be superscribed "Tender for constructing a block of four linemen's quarters at Kunigal Town, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Only 'Chamundi' Brand cement should be used on works.

14. Only Mysore teakwood should be used.

Abstract estimate for constructing a Block of Four Linemen's Quarters of Electrical Department at Kunigal Town.

No.	Items of work	Unit	Rate			Quantity
			Rs.	a.	p.	
1	Earthwork excavation in gravelly soil and filling in basement including watering and tamping in layers 6″ thick ..	C.yd.	0	3	6	29
2	Stone jelly (one inch thick) concrete in lime mortar 1 : 2 : 4 for foundation laid in 4″ layers and well tamped	C.ft.	0	3	6	309
3	Stone in lime mortar in courses not less than 8″ high with bond stones 6 feet apart in every course for foundations and for basement including all quoins dressed 2″ wide at corners ..	,,	0	4	3	741
4	Burnt brick in clay superstructure	,,	0	3	0	1,343
4(*a*)	Burnt brick in lime mortar	,,	0	4	6	700
5	Stone slabs 4″ to 6″ thick set in lime mortar with two line dressing for steps and all other exposed faces	S.ft.	0	5	0	150
6	Chunam plastering, two coats, inculding rounding off corners and smooth rendering	Sqr.	3	0	0	43.14
7	Cement pointing with thread lines after scraping the joints to ½″ to 1″ deep	Sqr.	3	8	0	1.50
8	White and colour washing, two coats	,,	0	4	6	44.64
9	Roofing with First Class Mangalore tiles on teak reepers nailed including wood oiling to reepers, eave tiles being tied by teak batten	Sqr.	25	0	0	15.00
10	Mangalore ridge tiles set in mortar and cement pointed complete	R.ft.	0	8	0	64
11	Ventilating tiles fixed complete double	Each	4	0	0	16
12	Teakwood wrought ad put up with wood oiling, two coats ..	C.ft.	5	0	0	61.55
13	Teakwood doors 3″×4″ with 1¼″ thick battened shutters all necessary iron fixtures complete	S.ft.	1	0	0	156

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
14	Teakwood windows with 3″×4″ frame, 1¼″ thick battened shutters, ⅝″ diameter iron bars 4″ apart and all necessary iron fixtures, etc., complete	S.ft.	1 4 0	75
15	Teakwood wall shelves 3″×4″ frame work with 1¼″ thick battened shutters and ¾″ cross planks, etc., complete ..	S.ft.	1 2 0	60
16	Chocolate painting, two coats (mixed and applied as per Bombay Specifications)	Sqr.	3 0 0	6.00
17	Constructing sinks in bath rooms	No.	5 0 0	4
18	Providing and fixing stone mortar and pestle	No.	5 0 0	4
19	Flooring with cement concrete 1 : 2 : 4 to 1½″ thick on a bed of 6″ thick lime concrete with topping of red cement ⅜″ thick finished and cut to required pattern where required ..	Sqr.	20 0 0	8.00
20	Levelling ground and clearing site and other unforeseen works	L. S.		

Notification dated 5th May 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 15th May 1939 for constructing 3 units of latrine at Kunigal Town for Electrical Department.

An approximate extimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer by paying four annas. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender should be accompanied by a treasury challan for Rs. 22 for having credited the amount of earnest money to "17 (*a*) P. W. Deposits" and be superscribed "Tender for constructing 3 units of Latrine at Kunigal Town," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Enigneer after working out data with not more than 10 per cent Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Only 'Chamundi' brand cement should be used on works.

14. Only Mysore Teakwood should be used.

Abstract estimate for constructing one Unit of Latrine for the Electrical Department at Kunigal Town.

No.	Item of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation (as per specifications)	C.yd.	0 3 6	4
2	Burnt size stone in clay in courses not less than 8″ high with bond stones 6 feet apart in every course for foundation and basement	C.ft.	0 3 6	130
3	Burnt brick in mortar superstructure	,,	0 4 6	196
4	Chunam plastering	Sqr.	3 0 0	5.00

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
5	Cement pointing basement alround	Sqr.	3 8 0	0·56
6	White and colour washing, two coats	,,	0 4 6	5·56
7	Cement plastering ½" thick alround	,,	7 0 0	0·79
8	Tarr washing, two coats	,,	1 8 0	0·63
9	Flooring with 3" concrete and cement plaster ½" thick latrite ..	,,	15 0 0	0·38
10	Fixing outlets and constructing drains	L. S.		
11	Providing galvanized iron sheet tubs 12"×6" complete with tarring	No.	1 0 0	6
12	Unforeseen charges	L. S.		

Notification dated 5th May 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 15th May 1939, for constructing Office and Stores for Electrical Department at Kunigal Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer by paying Re. 0-4-0. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury challan for Rs. 110 for having credited the earnest money to "17(a) P. W. Deposits" and be superscribed "Tender for constructing Office and Stores for Electrical Department at Kunigal Town," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Only 'Chamundi' brand cement should be used on works.

14. Only Mysore Teak should be used.

Abstract estimate for constructing Combined Station, Office and Stores for Electrical Department at Kunigal Town.

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation in gravelly soil and filling in basement including watering and tamping in layers 6" thick ..	C.yd.	0 3 6	39
2	Stone jelly (one inch size) in lime concrete (1 : 2 : 4) foundations laid in 4" layers and well consolidated	C.ft.	0 3 6	361
3	Stone in lime mortar in courses not less than 8" high with bond stones 6 feet apart in every course for foundations and for basement including all quoins dressed 2" wide at corners ..	C.ft.	0 4 3	869

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
4	Burnt brick in clay for superstructure	C.ft.	0 3 0	1,298
5	Burnt brick in mortar for superstructure	C.ft.	0 4 6	144
6	Burnt stone slabs 6″ thick set in lime mortar with two line dressing for outer walls and steps and one line dressing for all other faces	S.ft.	0 5 0	177
7	Stone slabs 3″ thick exposed parts one line dressed and set in mortar	S.ft.	0 4 0	7
8	Burnt brick in mortar pillars 1′–1½″ square and 9′–9″ high including stone base and capital and cement plastering ½″ thick, etc., complete	No.	15 0 0	4
9	Chunam plastering, two coats including rounding of corners and smooth rendering	Sqr.	3 0 0	29.00
10	Cement pointing with thread lines after scraping the joints to ½″ to 1″ deep	Sqr.	3 8 0	1.88
11	White and colour washing, two coats, as per plastering and pointing	Sqr.	0 4 6	31
12	Burnt brick in mortar cornice 9″ deep with 6″ projection as per design including chunam plastering	R.ft.	0 9 0	158
13	Plain parapet wall with burnt brick in mortar 9″ thick; 1¼′ to 2½′ high including blocking course 6″ high with weep holes 8 feet apart including plastering with chunam mortar.	R.ft.	0 10 0	155
14	Chunam moulding in front of wall between pillars	No.	5 0 0	3
15	Chunam moulding 6″×½″ alround ventilators ..	R.ft.	0 2 0	77
16	Flooring with cement concrete 1 : 2 : 4 to 1½″ thick on a bed of 6″ thick lime concrete with topping of red cement ⅜″ thick finished and cut to required pattern where required ..	Sqr.	20 0 0	6.00
17	Roofing with brick nogged terrace filled in with brick in surki mortar with wedge shaped precast R.C. joists with 3″ to 6″ surki concrete two courses of flat tiles surface and ceiling plastered with chunam, etc., complete below 10 feet span ..	Sqr.	55 0 0	6.75
18	Tested rolled steel girders as per B.S.S. including lifting and hoisting with two coats of approved paint with necessary clamps, etc., complete	Cwt.	12 0 0	18.5
19	Teakwood door with 3″×5″ frame work 1½″ thick panel shutters including four hold fasts of flat iron 15″×1½″×⅜″ iron fittings, rain door locks with handles, etc., complete ..	S.ft.	1 6 0	92
20	Teakwood windows with glazed shutters 1″ thick with iron bars ⅝″ diameter 4″ apart with necessary iron fixtures, etc., complete in four halves	S.ft.	1 10 0	70
21	Teakwood ventilators fully glazed with iron bars, etc., complete	S.ft.	1 4 0	27
22	Chocolate painting, two coats (mixed and applied as per Bombay specifications)	Sqr.	3 0 0	12.87
23	Fixing with wire guage shutters with teakwood reepers complete	S.ft.	1 4 0	63
24	Rain water down zinc pipes 4″ diameter including suitable bell mouth at top and bent at bottom	R.ft.	0 8 0	78
25	Brick in lime mortar and stone slabs with chunam plastering, etc., comlpete for brackets	L. S.		
26	Clearing site and levelling ground	L. S.		

P. RAJAGOPALAN,
Executive Engineer.

MANDYA DIVISION.

Notification dated 29th April 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 noon on 20th May 1939, for extending the Municipal High School at Mandya.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mandya Division, should be addressed to the Executive Engineer, Mandya Division, in a sealed cover and superscribed as "Tender for extending the Municipal High School at Mandya." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by Treasury challan for an earnest money of Rs. 700 paid to the Treasury in cash or Government Promissory Notes or Mysore Government Bonds, duly